REQUEST FOR QUOTATION (RFQ)

Ref. No.: DBRANLU/C&M/140/RFQ-1 **Date: 02.06.2026**

Subject: REQUEST FOR QUOTATION FOR CONSTRUCTION OF TEMPORARY TOILET AT G.F. NEAR STAIR IN HOSTEL AT DBRANLU, SONEPAT

Dr. B.R. Ambedkar National Law University, Sonepat, Haryana invites quotations from eligible **contractors/firms/agencies** for the **construction of temporary toilet at ground floor near stair in hostel** at University Campus, Rai, Sonepat.

1. Scope of Work

The scope of work includes **civil, sanitary, plumbing and finishing works** such as:

- Brick masonry work
- RCC work with reinforcement
- Flooring (cement + vitrified tiles)
- Plastering, putty & painting
- Door & frame fixing
- Sanitary fittings (WC, wash basin, urinal, etc.)
- Plumbing work (GI pipes, fittings, valves)
- Drainage & inspection chamber work

The work shall be executed strictly as per **HSR (Haryana Schedule of Rates)** and directions of Engineer-in-Charge.

2. Bill of Quantity (BOQ)

The detailed BOQ (as attached/provided) includes **HSR items + NS items** with estimated cost approx:

Estimated Cost: ₹1,45,124/-

Note:

- Payment shall be made on **actual executed quantity basis**

3. Terms & Conditions

1. The interested contractors/firms may submit their quotation in sealed envelope or via email to:
   constructionandmaintenance@dbranlu.ac.in
2. Last date of submission: **18.06.2026 up to 04:00 PM**
3. Envelope should be superscribed as:
   "QUOTATION FOR TEMPORARY TOILET WORK IN HOSTEL"
4. The quotation must include:
   - PAN Card
   - GST Registration

- Enlistment of Civil Works
- Experience (if any)

5. The rates must include **all material, labour, transportation, loading/unloading and taxes**.
6. The work must be completed within **40 days from issue of work order**.

4. Payment Terms

1. No advance payment shall be made.
2. Payment will be released after:
    - Successful completion of work
    - Certification by Engineer/Inspection Committee
3. Applicable GST will be paid as per rules.

5. Penalty Clause

1. Penalty clause will be applicable as per University Accounts Code Clause no. 12.67 (In case, the material/work is not supplied/executed within the supply/work compensation amount equal to 1% of the cost of the material/contract per day, provided that the total amount of compensation shall not exceed 10% of the total cost of the material/contract. After the lapse of 15 days beyond the stipulated/extended period, it will be the discretion of the University to cancel the supply/work execution order at the risk and cost of the supplier/contractor).

6. Warranty / Defect Liability

- Contractor shall be responsible for **defects for 6 months** from completion
- Any defect must be rectified **within 7 days** at no extra cost

7. Validity of Rates

- Quoted rates shall remain valid for **90 days**

8. Jurisdiction

- All disputes shall be subject to **Courts at Sonepat**.

9. Site Visit

- The vendors/firms may visit the site between 09:00 AM to 05:00 PM to see/check the location prior to submission of rates by them.

10. Company / Firm Details

Name of Firm:
Address:
Contact Person & Mobile:
Email:
GST No.:

Financial Bid

Sr. No.	HSR No		Qty	Unit
1	7.28.2	Half brick masonry with common burnt clay non-modular bricks of class designation 10.5 in superstructure above plinth level up to floor IV level. Cement mortar 1:4 (1 cement :4 coarse sand)	11.05	sqm
2	6.2.1	Providing and laying cement concrete in retaining walls, return walls,walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets,coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor four level, excluding the cost of centering, shuttering and finishing: 1:1½:3 (1 cement : 1½ coarse sand (zone-III) : 3 graded stone aggregate 20 mm nominal size)	0.11	cum
3	6.34.3	Steel reinforcement for R.C.C. work, where not included in the complete rate of RCC, including straightening, cutting, bending, placing in position, binding, wastage, overlaps, welded joints, spacer bars, chairs, stays, hangers and annealed steel wire etc. complete in all respect above plinth level.Cold twisted bars	9.9	kg
4	6.30.5	Centering and shuttering including strutting, propping etc. and removal of form for Lintels, beams, plinth beams, girders, bressumers and cantilevers	2.1	sqm
5	5.44	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead	5.18	sqm
6	5.45	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead	9.66	sqm
7	10.10.2 (-)10.14	Providing and laying Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete	4.63	sqm

8	10.63.2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	4.63	sqm
9	10.67.2	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours and shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement and matching pigments etc. complete.Size of Tile 600x600 mm	28.8	sqm
10	11.8	12 mm cement plaster of mix :1:4 (1 cement: 4 coarse sand)	15.53	sqm
11	11.58	Providing and applying two coats white cement based putty of approved brand and manufacturer, over plastered surface and grinding the surface smooth with sand paper to get en even and smooth finish including cost and carriage of all material , labour charges, scaffolding, sundries etc. complete	15.53	sqm
12	11.65	Distempering with 1st quality acrylic distemper (ready mixed) having VOC content less than 50 gms/litre, of approved manufacturer, of required shade and colour complete, as per manufacturer`s specification.	15.53	sqm
13	30.34	Distempering with 1st quality acrylic distemper (ready made) having VOC content less than 50 gm per litre. of approved manufacturer and of required shade and colour complete. as per manufacturer`s specification.Two or more coats on new work	54.72	sqm
14	13.2	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel Angle sections of size 35x35x5 mm, joints mitred and welded by angle iron 35x35x5 mm or 35x 5 mm flat pieces to the existing T-iron frame or to the wall with dash fastener, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer, all complete as per the direction of Engineer-In-charge.	40	kg
15	13.6.1	Providing and fixing 1mm thick M.S. sheet door with frame of 40x40x6 mm angle iron and 3 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer Using M.S. angels 40x40x6 mm for diagonal braces	3.25	sqm
16	11.82	Painting the wooden / metal surface with synthetic enamel paint of approved brand and manufacture to give an even shade Two or more coats on new work	3.25	sqm

17	30.28.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade One or more coats on old wor	11.27	sqm
18	12.65.2	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : 250x16 mm	2	Each
19	12.66.1	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : 250x10 mm	4	Each
20	12.69.2	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete 100 mm	4	Each
21	22.1.4	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:White vitreous chinaware Flat back wash basin size 550x 400 mm with single 15 mm C.P. brass pillar tap	1	Each
22	22.14.1	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete..1 Semi rigid pipe 32 mm dia	2	Each
23	22.209	Providing and fixing 600x450 mm bevelled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete.	1	Each
24	22.26.1	Providing and fixing white vitreous chinaware flat back half stall urinal of size 580x380x350 mm with white PVC flushing cistern, with fittings, standard size C.P. brass flush pipe, spreaders with unions and clamps (all in C.P. brass) with waste fitting as per IS : 2556, C.I. trap with outlet grating and other couplings in C.P. brass, including painting of fittings and cutting and making good the walls and floors wherever required : Single half stall urinal with 5 litre P.V.C. automatic flushing cistern	1	Each
25	22.23.1	Providing and fixing white vitreous chinaware pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid	2	Each
26	22.102.2	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet : 150 mm diameter	2	Each
27	22.101.2.1	Providing and fixing Unplasticised PVC connection pipe with brass unions : 30 cm length 20 mm nominal bore	6	Each
28	22.104.1	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 : 15 mm nominal bore	2	Each
29	22.106.1	Providing and fixing C.P. brass long body bib cock of approved quality conforming to IS standards and weighing not less than 690 gms. 15 mm nominal bore	2	Each

30	22.107.1	Providing and fixing C.P. brass stop cock (concealed) of standard design and of approved make conforming to IS:8931 15 mm nominal bore	2	Each
31	22.108.1	Providing and fixing C.P. brass angle valve for basin mixer and geyser points of approved quality conforming to IS:8931 15mm nominal bore	4	Each
32	22.20.2	Providing and fixing in position C.I. plain Nahani Trap conforming to I.S.I. specifications and of self cleaning design with C.P. brass hinged grating with frame complete With 75 mm internal diameter outlet	6	Each
33	22.38	Providing and fixing 8 mm dia C.P. / S.S. Jet with flexible tube up to 1 metre long with S.S. triangular plate to European type W.C. of quality and make as approved by Engineer - in - charge.	2	Each
34	22.82.1	Cutting holes up to 30x30 cm in walls including making good the same: With common burnt clay non-modular bricks	2	Each
35	22.90	Making chases up to 7.5x7.5 cm in walls including making good and finishing with matching surface after housing G.I. pipe etc.	30.48	Mtr
36	22.89.1	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall : 15 mm dia nominal bore	30.48	Mtr
37	22.89.2	Providing and fixing G.I. Pipes complete with G.I. fittings and clamps, i/c making good the walls etc. concealed pipe, including painting with anti corrosive bitumastic paint, cutting chases and making good the wall 20 mm dia nominal bore	9.14	Mtr
38	22.94.2	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) 20 mm nominal bore	1	Each
39	21.84.1	Constructing brick masonry inspection Chamber sizes as given below up to 0.60 metre average depth in cement mortar 1 :5 lime concrete with 40 per cent lime mortar 2:3 in foundation cement concrete 1 :2:4 benching 12mm thick cement plaster 1 :2 with a floating coat of 1 mm thick of neat c ement R.C.C. 1 :2:4 slab 100 mm thick/cement concrete topping, 50mm thick: with 455mmx455mm / 455mm x610mm inside light duty C.I. inspection chamber cover and frame weight as per 1.5.1. specification painted with 3 coats of black bitumastic superior paint complete as per standard design. Size 450 mm X450 mm inside (with 455 mm x 455 mm cover and frame light duty single seal weighing 20 kg with C.C. topping	1	Each
40	22.92.1	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete : 25 to 40 mm nominal bore	1	Each
41	22.152.1	Providing and laying SandS centrifugally cast (spun) iron pipes (Class LA) conforming to IS - 1536 100 mm dia pipe	21	Mtr

42	22.153.1	Providing lead caulked joints to spun iron or C.I. pipes and specials, including testing of joints but excluding the cost of pig lead : 100 mm diameter pipe	8	Each
43	22.156.2	Labour for cutting C.I. pipe with steel saw. 100 mm diameter C.I. pipe	7	Each
44	22.154	Supplying pig lead at site of work.	0.04	Quintal
45	22.157.1	Providing and laying SandS C.I. Standard specials such as tees, bends, collars tapers and caps etc, suitable for flanged jointing as per IS : 1538 : Up to 300 mm dia	0.2	Quintal
46	6.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work below plinth level and up to Floor IV level: 1:2:4 (1 cement : 2 coarse sand (zone-III) : 4 graded stone aggregate 20 mm nominal size)	0.25	cum
NS Items				
1		Providing and fixing C.P. Jali	6	Nos
HSR Items Total Amount		121289		

Sr. no	Items	Rate Quoted by Firm above/below % on HSR Rate	Total Amount
1	**CONSTRUCTION OF TEMPORARY TOILET AT G.F. NEAR STAIR IN HOSTEL AT DBRANLU, SONEPAT**		
NS Items			
Sr. No	**Items**	Rate Quoted by Firm	Total Amount
1	Providing and fixing C.P. Jali		

10. Financial Bid Declaration

I/We agree to execute the above work as per BOQ and terms & conditions of DBRANLU.

Signature: _____
Stamp: _____